



September 13, 2007

Ms. Jennifer Hale Weyerhaeuser Company P.O. Box 9777 Mail Stop WTC-2G2 Federal Way, WA 98063-9777

Subject: 12th Street Landfill – Emergency Action

Status Update Report

Dear Jennifer:

This letter presents activities performed as part of the 12th Street landfill emergency action in Plainwell, Michigan, between September 1 and September 10, 2007. Equipment delivered to the site over this period included the final sheeting for the Portadams, 20,000-gallon storage tank, 200 gpm water treatment system, and off road dump truck.

Safety issues covered during daily meetings included equipment safe zones, water safety, rigging safety, lifting procedures, equipment maintenance, hydraulic operations, heat stress, poison ivy, and general site safety issues.

Field activities performed during this period include the following:

- Completed the pad area for the storage tank and water treatment system.
- Set roll off box in river for secondary water containment. Placed double silt curtains around roll off.
- Placed curtain material on the Portadam structures. Placed continuous line of sandbags along edge of Portadam curtain.
- Placed concrete manhole into channel and placed pump into manhole. Began pumping down channel.
- Once area pumped down, sediments were removed starting at peninsula area and working back toward shoreline. Approximately 600 cubic yards of sediment were removed. Areas of residuals identified near peninsula and in sporadic locations along shoreline. All visual residuals removed and transported to containment pad.
- Sampling stations installed within the river to monitor turbidity were operated throughout the construction activities. The upstream monitoring station was located on the dam side of the small peninsula across the powerhouse channel from the landfill. The downstream monitoring location was approximately 200 feet downstream from the Portadam and 15 feet from the river's edge. Sample results were reviewed several times per day during excavation activities.
- The water quality control performance criterion to trigger corrective responses was a consistently visible plume or reproducible turbidity readings at the downstream station that was 2 times the background water quality. Background readings taken from August 22 to 24, 2007, had levels of 16 to 18 NTUs. However, at start of construction, background turbidities had fallen and ranged from 2 to 4 NTUs. Periodically during the excavation activities, downstream levels exceeding twice the upstream level were identified. The maximum average hourly turbidity reading downstream of the construction area was 15.4 NTUs. As turbidity increases were identified, modifications to construction were performed which included shutting pump down, decreasing pump volume, reconfiguring roll off box with additional dissipation for more uniform flow out of box, and added an additional silt curtain adjacent to roll off to assist in capturing

Ms. Jennifer Hale Weyerhaeuser Company September 13, 2007 Page 2

resuspended sediment. These actions slowed the emergency excavation activities. Both a tabular summary of turbidity data and a graphical representation of these results are attached to this report.

- Initial removal of sediment in channel was completed on September 10, 2007. Sampling of the channel was performed on September 11, 2007. Pumping of the area will continue to keep static head on Portadams until analytical results are received.
- Bank area was regraded to approximately 3:1 slope. Bank is consistently sand and gravel.

If you have any questions regarding RMT's services, please contact me at 262-879-1212.

Sincerely,

RMT, Inc.

James L. Hutchens Sr. Project Manager

cmk/enclosures

cc: Michael Berkoff, USEPA Jeff Kaiser, CH2M Hill Paul Bucholz, MDEQ



Client Name:Site Location:Project No.:Weyerhaeuser Company12th Street Powerhouse Channel00-05131.04

 Photo No.
 Date

 1
 9/4/07

Description

Portadams prior to installing sheeting



Photo No. Date 2 9/5/07

Description

Fabric Placement upstream





Client Name:Site Location:Project No.:Weyerhaeuser Company12th Street Powerhouse Channel00-05131.04

 Photo No.
 Date

 3
 9/5/07

Description

Placing sandbags on portadam upstream



 Photo No.
 Date

 4
 9/5/07

Description

Lay out curtain upstream





Client Name:Site Location:Project No.:Weyerhaeuser Company12th Street Powerhouse Channel00-05131.04

Photo No. Date 5 9/6/07

Description

Portadam placement downstream




Photo No. Date 6 9/6/07

Description

Place manhole for pumping channel





Client Name:Site Location:Project No.:Weyerhaeuser Company12th Street Powerhouse Channel00-05131.04

 Photo No.
 Date

 7
 9/6/07

Description

Pump set within manhole



 Photo No.
 Date

 8
 9/6/07

Description

Remove material from peninsula area





Client Name:Site Location:Project No.:Weyerhaeuser Company12th Street Powerhouse Channel00-05131.04

 Photo No.
 Date

 9
 9/7/07

Description

Peninsula area after excavation



 Photo No.
 Date

 10
 9/8/07

Description

Dissipation tank and secondary containment area





Client Name:Site Location:Project No.:Weyerhaeuser Company12th Street Powerhouse Channel00-05131.04

 Photo No.
 Date

 11
 9/8/07

Description

Material within containment pad



 Photo No.
 Date

 12
 9/9/07

Description

Bank area begin reshaping



Turbidity Data Powerhouse Channel - Plainwell, Michigan

Date	Time	Turbidity - NTU		namer - Hamwen, Mienigan	
m/d/y	hh:mm:ss	Upstream	Downstream	Comments	
·				Turbidity readings taken 8/22 to 8/24 at 15-minute intervals resulted in	
		Hourly Avg	Hourly Avg	average turbidty of 16.0 upstream and 17.7 downstream.	
9/5/2007	12:45:40	4.6	0.9		
9/5/2007	13:45:40	5.2	1.4		
9/5/2007	14:45:40	4.6	2.8		
9/5/2007	15:45:40	3.5	1.5		
9/5/2007	16:45:40	2.9	0.4		
9/5/2007	17:45:40	2.3	0.0		
9/5/2007	18:45:40	2.1	0.0		
9/5/2007	19:45:40	1.9	0.0		
9/5/2007	20:45:40	2.0	0.0		
9/5/2007	21:45:40	2.4	0.0		
9/5/2007	22:45:40	2.8	0.0		
9/5/2007	23:45:40	3.1	0.0		
9/6/2007	0:45:40	3.1	0.0		
9/6/2007	1:45:40	3.0	0.0		
9/6/2007	2:45:40	3.1	0.0		
9/6/2007	3:45:40	3.0	0.0		
9/6/2007	4:45:40	3.5	0.0		
9/6/2007	5:45:40	2.9	0.0		
9/6/2007	6:45:40	3.1	0.0		
9/6/2007	7:45:40	3.3	0.5		
9/6/2007	8:45:40	2.4	0.0		
9/6/2007	9:45:40	2.0	0.0		
9/6/2007	10:45:40	1.6	0.0	Begin slow pumping to seat Portadam curtains.	
9/6/2007	11:45:40	1.3	0.0		
9/6/2007	12:45:40	1.2	0.0		
9/6/2007	13:45:40	0.7	0.0	D :	
9/6/2007	14:45:40	0.6	0.0	Begin pumping to dewater at approximately 2,000 gpm.	
9/6/2007	15:45:40	1.2	1.9		
9/6/2007	16:45:40	1.1	0.0		
9/6/2007	17:45:40	0.5	0.0		
9/6/2007 9/6/2007	18:45:40 19:45:40	0.4	0.0		
9/6/2007	20:45:40		0.0		
9/6/2007	20:45:40	0.0	0.0		
9/6/2007	22:45:40	1.3	0.0		
9/6/2007	23:45:40	1.5	0.0		
9/7/2007	0:45:40	1.8	0.0		
9/7/2007	1:45:40	2.0	0.0		
9/7/2007	2:45:40	2.0	0.0		
9/7/2007	3:45:40	2.3	0.0		
9/7/2007	4:45:40	2.3	0.0		
9/7/2007	5:45:40	2.4	0.0		
9/7/2007	6:45:40	2.5	0.0		
9/7/2007	7:45:40	2.6	0.4	Area pumped down begin to see turbidity within curtained area.	
9/7/2007	8:45:40	2.0	10.7		
9/7/2007	9:45:29	1.4	3.7	Shut down pump.	
9/7/2007	10:45:40	1.7	4.2		
9/7/2007	11:45:40	1.8	5.1		
9/7/2007	12:45:40	1.6	11.4	Modify secondary containment area, level discharge box.	
				Increase in turbidity from working within containment area reanchoring	
9/7/2007	13:45:40	1.8	0.2	sheet curtains.	
			L.	La contraction of the contractio	

Turbidity Data							
Powerhouse	Channel	- Plainwell,	Michigan				

	Date	Time	Turbidi	ty - NTU	Comments
	m/d/y	hh:mm:ss	Upstream	Downstream	Comments
9	9/7/2007	14:45:40	4.5	0.7	
9	9/7/2007	15:45:40	3.5	4.3	
(9/7/2007	16:45:40	2.2	4.4	Restart pump to maintain level.
	9/7/2007	17:45:40	1.8	3.4	• •
	9/7/2007	18:45:40	3.1	3.5	
	9/7/2007	19:45:40	2.5	3.8	
(9/7/2007	20:45:40	2.3	3.4	
(9/7/2007	21:45:40	2.7	3.3	
	9/7/2007	22:45:40	3.3	3.7	
	9/7/2007	23:45:40	3.6	4.0	
	9/8/2007	0:45:40	3.8	4.3	
	9/8/2007	1:45:40	3.9	4.6	
	9/8/2007	2:45:40	4.1	4.8	
	9/8/2007	3:45:40	4.1	5.0	
	9/8/2007	4:45:40	4.4	5.0	
	9/8/2007	5:45:40	4.3	4.8	
	9/8/2007	6:45:40	4.4	11.4	Resume pumping at 2,000 gpm.
	9/8/2007	7:45:00	4.3	7.8	Pump level closer to sediment interface beginning to create turbidity within silt curtain.
-	9/8/2007	8:45:40	3.8	6.9	
	9/8/2007	9:45:40	3.2	12.0	
	9/8/2007	10:45:40	2.8	9.1	Shut pump down @ 9:20.
	9/8/2007	11:45:40	2.5	9.5	Work on containment area to move curtains further from discharge box. Restart pump.
(9/8/2007	12:45:40	2.9	5.2	
	9/8/2007	13:45:40	1.8	10.4	Shut down pump.
	9/8/2007	14:45:40	2.6	3.0	Modify discharge box. Clean out sediments, add drum to end of disharge to allow more uniform flow out of box.
(9/8/2007	15:45:40	2.1	5.5	Restart pump and bring to full flow.
(9/8/2007	16:45:40	1.5	3.8	
(9/8/2007	17:45:40	1.2	7.0	Shut down pump @ 5:30.
(9/8/2007	18:45:40	1.3	2.8	
	9/8/2007	19:45:40	1.7	5.1	
	9/8/2007	20:45:40	6.3	4.2	
	9/8/2007	21:45:40	3.8	4.7	
(9/8/2007	22:45:40	4.7	5.6	
	9/8/2007	23:45:40	5.3	6.2	
	9/9/2007	0:45:40	5.9	7.0	
	9/9/2007	1:45:40	6.4	7.5	
	9/9/2007	2:45:40	6.8	7.9	
	9/9/2007	3:45:40	7.0	8.4	
	9/9/2007	4:45:40	7.6	8.7	
	9/9/2007	5:45:40	8.1	9.0	
	9/9/2007	6:45:40	8.1	9.1	Water up approximately 1 foot since yesterday.
	9/9/2007	7:45:40	8.2	9.2	Shut down pump and move intake.
	9/9/2007	8:45:40	7.2	9.5	
	9/9/2007	9:45:40	6.3	8.0	Restart pump @ 9:15, high turbidity.
	9/9/2007	10:45:00	5.9	15.4	Shut down, clean out culvert, and reset pump.
	9/9/2007	11:45:40	5.5	9.8	,
	9/9/2007	12:45:40	4.8	7.9	Restart pump. Initial turbidity clearing up quickly.
	9/9/2007	13:45:00	4.2	11.2	, p
	9/9/2007	14:45:00	4.1	4.9	Shut down pump @ 2:00.

